



MERCED COMMUNITY COLLEGE DISTRICT

Chuck Hergenraeder, Purchasing Manager

3600 M Street, Merced, California 95348-2898

Telephone: 209/384-6300 • Fax: 209/384-6310

BID ADDENDUM

DATE: 9/22/17

BID No: 2017-11

BID TITLE: FOOD FOREST CONCRETE PROJECT

ADDENDUM 1

This addendum contains clarification and additional information, which modifies the conditions of the above referenced BID as follows:

Information from Pre-Bid Job Walk-

1. Days to Completion – 60 days
2. Engineer's Cost Estimate - \$ 98,500.00
3. Color of decomposed granite material - Gray
4. What is the rough grade – Plus or Minus 0.2 feet
5. What is the drain pipe preparation – Pipeline Material is as per the specification section 02430 and the preparations shall be 7/8-inch diameter holes placed at 4 o'clock and 8 o'clock, spaced every 6 inches.
6. Construction Staking to be provided by Owner through QK, project Engineer
7. Sign-in Sheet Attached
8. Subbase under Concrete walks – Contractor to place 4 inches of Class 2 Aggregate Base material compacted to 95%
9. 2-3" Mulch; 6" Imported Top Soil, 12-18" Imported Top Soil as per sheet plan C3 are alternate bid items – Not a part of this bid
10. Concrete walks and paving as per sheet plan C3 – psi? with color? With stamp? See Specifications for concrete strength 03302, 2.01, color and Stamp pattern as per General Note No. 1 Sheet C2.
11. Concrete Seat Wall is an Alternate bid item? Concrete with color? With stamp? – Seat wall is bid item #9 on revised bid schedule
12. Clarify location and length of Seat Wall in sheet plan C2 – Location and length to be staked in the field, total length given in Bid Item
13. DG material is gray color? With stabilizer? with header boards? With weed barrier? DG color is Gray, with Stabilizer, with header board being a 2" by 4" recycled Plastic material from Bender Board Landscape Products, Riverbank CA, (604) 946-7805, with weed barrier.

All other bidding contract and construction drawing documents, stipulations, dated and times remain unchanged, in full effect and by reference become a part of this addendum.

TO ALL HOLDERS OF PLANS, CONTRACT DOCUMENTS, AND SPECIFICATIONS:

This addendum forms a part of the Contract and modifies the original Plans dated September 2017 as noted below:

Contract Documents and Specifications -

1. Bid Proposal page; replace with enclosed page, Section 0000
2. EXPLANATION OF BID ITEMS; Replace with attached two (2) pages, Section 0000

SPECIAL NOTE:

It is the responsibility of each Bidder to acknowledge all addenda by signing below and submitting a copy of each addendum with their respective bid.

I HAVE READ AND UNDERSTAND THESE MODIFICATIONS TO THE ABOVE BID: _____

All other bidding contract and construction drawing documents, stipulations, dated and times remain unchanged, in full effect and by reference become a part of this addendum.



LBC, FOOD FOREST CONCRETE PROJECT, Bid #2017-11

SEPTEMBER 19, 10:00am

Sign in Sheet

Merced Community College Purchasing

	Vendor Name	Sign Name	Phone Number	Email Address
1	DAQUENRO CONST	Ben Jaques	(209) 777-4306	ON FILE
2	Adrian C	[Signature]	209 604 4726	adrian@cgboise.com
3	Romero Concrete	Ubaldo Romero	709 956 0131	Romero Concrete & Retention
4	ROBERT FEHL B-2	[Signature]	209-531-1252	ON FILE
5	Doon Inc	[Signature]	(209) 376-8382	charles@doon.com
6	Sandra Gallardo	[Signature]	559 434-6182	office@hambosc.com
7	R&M CONSTRUCTION Garth P	[Signature]	559 492-1252	JBELMONT@RMCNSTORLY
8	Garth Beckham	[Signature]	(209) 723-2066	garth.beckham@ghinc.com
9				
10				
11				
12				
13				

*** BID FORM**

TO: Merced Community College, acting by and through its Governing Board, herein called "COLLEGE".

1. Pursuant to and in compliance with your Notice Inviting Bids and other documents relating thereto, the undersigned bidder, having familiarized himself with the terms of the contract, the local conditions affecting the performance of the contract and the cost of the work at the place where the work is to be done, hereby proposes and agrees to perform within the time stipulated, the contract, including all of its component parts, and everything required to be performed, including its acceptance by the COLLEGE, and to provide and furnish any and all labor, materials, tools, expendable equipment, and utility and transportation services necessary to perform the contract and complete all of the work in a workmanlike manner required in connection with the construction of Modifications for Abandoned Wastewater Treatment Plant Project in the COLLEGE described above, all in strict conformance with the drawings and other contract documents on file at the Purchasing Office of said COLLEGE for amounts set forth herein.

2. ADDENDA: The undersigned has thoroughly examined any and all Addenda (if any) issued during the bid period and is thoroughly familiar with all contents thereof and acknowledges receipt of the following Addenda: (Bidder to list all addenda).

ADDENDUM NO. _____
 ADDENDUM NO.

DATE RECEIVED _____
 DATE RECEIVED _____

3. BASE BID

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL PRICE
1	MOBILIZATION	1	LS	\$	\$
2	EARTHWORK	1	LS	\$	\$
3	CONCRETE WALKS & AREAS	1270	SF	\$	\$
4	4" CRUSHED GRAVEL/DG WALKS	3610	SF	\$	\$
5	FRENCH DRAIN	230	LF	\$	\$
6	HANDI-CAP STRIPING/SIGNAGE	1	LF	\$	\$
7	3 inch IRRIGATION SLEEVES	13	EA	\$	\$
8	8-inch pipe	25	LF	\$	\$
9	Concrete Seat Wall	94	LF	\$	\$

BASE BID TOTAL CASH PURCHASE PRICE IN WORDS & NUMBERS:

_____ DOLLARS
 (\$ _____)

Note: It is COLLEGE.'s intention to award the project to the lowest qualified bidder for the base bid.

4. EXPLANATION OF BID ITEMS:

Item No. 1 - Mobilization

The price paid shall include full compensation for mobilization of materials, equipment, tools and labor necessary to complete the project as detailed and specified on the plans.

Item No. 2 – Earthwork

The price paid shall include full compensation for grading, shaping and placing soils as detailed and shown on the plans, including but not limited to, cutting, filling, compaction and testing of subgrade, and all such other costs as are considered essential for the completion of the improvements.

Item No. 3 – Concrete Walks & Areas

The price paid shall include full compensation for all materials, labor and equipment necessary to install concrete walks and concrete areas and all such other work as required for a complete and proper installation as shown on the plans and specified herein. Engineer shall have the right to request testing of any materials used in concrete placement to determine if they are of the quality specified. Concrete walks and area installations to have compaction tests completed as directed by Owner and all such other costs as are considered essential to the installation of the concrete material.

Item No. 4 – 4” Crushed Gravel/DG Walks

The price paid shall be considered as full compensation for all materials, labor and equipment necessary to install crushed gravel/Decomposed Granite material and all such other work as required for a complete and proper installation as shown on the plans and specified herein. Engineer shall have the right to request testing of any materials used in walk surface to determine if they are of the quality specified. Decomposed Granite installation to have compaction tests completed as directed by Owner and all such other costs as are considered essential to the installation of the backfill material.

Item No. 5 – French Drain

The price paid shall be considered as full compensation for all materials, labor and equipment necessary to install French Drain and all such other work as required for a complete and proper installation as shown on the plans and specified herein. Engineer shall have the right to request testing of any materials used in French Drain trench rock installation to determine if they are of the quality specified. Placement of Filter fabric shall be reviewed by Engineer prior to trench backfill and placement of River Rock as shown on the plans. Upon completion all equipment, forming materials, and debris shall be removed from the site.

Item No. 6 – Handi-Cap Striping/Signage

The price paid shall include full compensation for parking stall markings, cross walk markings and signage as detailed and shown on the plans, including but not limited to,

cleaning of asphalt, removal of existing markings, placement of truncated domes, and all such other costs as are considered essential for the completion of the improvements.

Item No. 7 – Irrigation Sleeves

The price paid shall include full compensation for grading, shaping and placing irrigation sleeves as detailed and shown on the plans, including but not limited to, cutting, filling, compaction and testing of subgrade, and all such other costs as are considered essential for the completion of the improvements.

Item No. 8 – Drainage Pipe

The price paid shall include full compensation for installation of solid drainage pipe as detailed and shown on the plans, including but not limited to, cutting, filling, compaction and testing of subgrade, and all such other costs as are considered essential for the completion of the pipe crossing improvements.

Item No. 9 – Concrete Seat Wall

The price paid shall include full compensation for installation of Concrete Seat Wall as detailed and shown on the plans, including but not limited to, cutting, filling, compaction and testing of subgrade, forming, placement of reinforcement steel, placement of concrete, finishing of concrete and all such other costs as are considered essential for the completion of the concrete seat wall improvements.